

पत्रांक पटना / दिनांक

प्रेषक,

कार्यपालक अभियंता
लोक स्वास्थ्य प्रमण्डल, पटना पूर्व, पटना।

सेवा में,

मे० बम-बम सिंह,
ग्राम-मधरापुर, बरहपुर
अंचल-मोकामा, पटना।

विषय :

राष्ट्रीय ग्रामीण पेयजल कार्यक्रम (2013-14) अन्तर्गत पुराने एवं बंद चापाकल (सस्टेनेबल) के स्थान पर नये चापाकल का निर्माण एवं पाँच वर्षों तक रख-रखाव कार्य का कार्यादेश निर्गत करने के संबंध में।

महोदय,

उपरोक्त विषयांकित कार्य का दि० 11.02.14 को हुई निविदा में आपके उद्धृत दर का अनुमोदन अधीक्षण अभियंता, लोक स्वास्थ्य अभियंत्रण, पटना अंचल, पटना के पत्रांक 407 दि० 22.05.14 द्वारा किया जा चुका है। दर अनुमोदनोपरान्त आपके द्वारा जमानत की राशि जमा करते हुए एकरारनामा पर हस्ताक्षर कर दिया गया है। अतएव अधोहस्ताक्षरी द्वारा एकरारनामा सम्पादित किया जाता है। कार्य का एकरारनामा सं० F₂-03/2014-15 है एवं राशि 37,37,640.00 (सैंतीस लाख सैंतीस हजार छः सौ चालिस) मात्र है।

अतः आपको निदेशित किया जाता है, कि सहायक अभियंता, लोक स्वास्थ्य अवर प्रमण्डल, बाढ़/विश्वविद्यालय, पटना से सम्पर्क कर उनके देख-रेख में सात दिनों के अन्दर कार्य प्रारम्भ कर निर्धारित कार्यावधि अर्थात् चार माह के अन्दर समाप्त करना सुनिश्चित करें।

अन्य शर्त :-

1. कार्यादेश निर्गत की तिथि कार्य प्रारंभ करने की तिथि मानी जाएगी।
2. कार्य की लागत एवं मात्रा किसी भी परिस्थिति में एकरारनामा में प्रावधानित राशि एवं मात्रा से बढ़ा हुआ मान्य नहीं होगा तथा कार्य मानक विशिष्टताओं के अनुरूप सम्पादित होगा।
3. कार्यहित में जमानत की राशि के इरूटमेंट के सत्यापन की प्रत्याशा में एकरारनामा किया जा रहा है। जमानत की राशि के रूप में जमा की गई टी०डी०एस० पासबुक/एन०एस०सी० के सत्यापन के क्रम में यदि गलत पाया गया तो आपके विरुद्ध विधि सम्मत कार्रवाई की जाएगी एवं सत्यापन होने तक प्रथम विपत्र का भुगतान अवरुद्ध रहेगा।
4. कार्यादेश निर्गत की तिथि से बिना उचित कारण के यदि अविलंब कार्य प्रारम्भ नहीं किया जाता है तो एकरारनामा के रद्द करते हुए अग्रधन एवं जमानत की राशि को राज्यसात कर ली जाएगी।
5. एकरारनामा की प्रति संलग्न की जाती है।
अनु०-यथोपरि।

विश्वासभाजन्

ह०/-

कार्यपालक अभियंता

लोक स्वास्थ्य प्रमण्डल, पटना पूर्व, पटना।

ज्ञापांक:-

दिनांक:-

प्रतिलिपि:-

सहायक अभियंता, लोक स्वास्थ्य अवर प्रमण्डल, बाढ़/विश्वविद्यालय, पटना को एकरारनामा की एक प्रति सहित सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। निदेशित किया जाता है कि संवेदक से सम्पर्क कर कार्य प्रारम्भ कराना सुनिश्चित करें तथा प्रारंभ किए जाने की सूचना तथा पाक्षिक प्रगति प्रतिवेदन जमा करना सुनिश्चित करेंगे। कार्य में व्यवहार किए जाने के पूर्व सामग्री गुणवत्ता प्रतिवेदन से संतुष्ट होकर ही कार्य में व्यवहार की अनुमति देंगे तथा विपत्रों के साथ गुणवत्ता प्रतिवेदन की एक प्रति संलग्न कर प्रस्तुत करना चाहेंगे।

अनु०- यथोपरि

ह०/-

कार्यपालक अभियंता

लोक स्वास्थ्य प्रमण्डल, पटना पूर्व, पटना।

IT Manager
आलेख
26/6/14

ज्ञापांक:- दिनांक:-
प्रतिलिपि:- अधीक्षण अभियंता, लोक स्वास्थ्य अभियंत्रण, पटना अंचल, पटना को एकरारनामा प्रति के साथ सूचनार्थ एवं आवश्यक कार्रवाई हेतु सादर समर्पित।

अनु०-यथोपरि।

ह०/-

कार्यपालक अभियंता
लोक स्वास्थ्य प्रमण्डल, पटना पूर्व, पटना।

ज्ञापांक:- दिनांक:-
प्रतिलिपि:- सम्बद्ध लेखा लिपिक/रोकड़पाल को सूचनार्थ प्रेषित करते हुए निदेश दिया जाता है कि प्रथम विपत्र की एकरारनामा पर अंकित जमानत के इंस्ट्रूमेंट का सत्यापन प्रतिवेदन से संतुष्ट हो लेने के उपरांत तथा जमानत के इंस्ट्रूमेंट की इंटररेस्ट वियरिंग सिक्क्यूरिटी पंजी में प्रविष्टि पश्चात् ही भुगतान की कार्रवाई करेंगे।

ह०/-

कार्यपालक अभियंता
लोक स्वास्थ्य प्रमण्डल, पटना पूर्व, पटना।

ज्ञापांक:- दिनांक:-
प्रतिलिपि:- महालेखाकार (ले० एवं हक०) बिहार, पटना को एकरारनामा प्रति के साथ सूचनार्थ समर्पित।

अनु०-यथोपरि।

ह०/-

कार्यपालक अभियंता
लोक स्वास्थ्य प्रमण्डल, पटना पूर्व, पटना।

ज्ञापांक:- 976 दिनांक:- 18.6.14
प्रतिलिपि:- प्रभारी पदाधिकारी, बिहार राज्य जल एवं स्वच्छता मिशन, पटना को विभागीय निदेशानुसार कार्यादेश प्रति विभागीय वेबसाइट पर प्रकाशनार्थ समर्पित।

अनु०-यथोपरि।

कार्यपालक अभियंता
लोक स्वास्थ्य प्रमण्डल, पटना पूर्व, पटना।

संजिव
18/6/14

Govt of Bihar
PUBLIC HEALTH ENGINEERING DEPARTMENT
P.H. DIVISION PATNA EAST

Agreement for the Work : Construction of 24 Nos. of 125mm × 40mm × 46M, 48 Nos. of 125mm × 40mm × 61M deep Hand Tube well with IM-II Hand pump, Platform & drain including Operation & Maintenance for 5-years in Place of Old & Defunct Hand Pumps in Patna Distt. under P.H.D., Patna East. Patna under NRDWP for the year 2013-14.

Certified Copy

NAME OF AGENCY :- M/s Bambam Singh,
Vill.-Madhrapur, Barahpur, Anchal - Mokama, Patna

Bambam Singh
18/6/14
P.H. Division Patna East

AGG. NO. AND YEAR : F₂-03/2014-15

DATE OF WORK ORDER:- 18/6/14
-976 dt. 18.6.14

TIME OF COMPLETION:- 4 (Four) Months

AGREEMENT VALUE:- Rs. 37,37,640.00

Construction of 24 Nos. 125mm × 40mm × 46M deep Tube Well with I.M.-II Hand Pump, Platform & drain including Operation & Maintenance for 5 years in Patna district.

S. N.	Particulars	Qty.	Unit	Rate	Rate in Words
1	CONSTRUCTION OF 125MM X 40MM X 46M DEEP TWELL				
Part 'A' Cost of Materials					
1	I.S.I Marked India mark II hand pump with 8 Nos. Connecting Rod and one cylinder confirming IS:15500 (Part 1-8)/2008	24 No.	Each	Rs.9,284.00	Rupees Nine Thousand Two Hundred Eighty Four Only
2	I.S.I Marked 125mm dia U.P.V.C casing pipe confirming to IS.12818-1983/1992	648 M	P/M	Rs.432.00	Rupees Four Hundred Thirty Two Only
3	I.S.I Marked 32 mm dia G.I. pipe medium quality (3mtr each length) confirming IS.1239(Part 1-4)	576 M	P/M	Rs.234.00	Rupees Two Hundred Thirty Four Only
4	I.S.I Marked 40mm dia best quality UPVC pipe conforming to IS.12818-1983/1992	360 M	P/M	Rs.80.80	Rupees Eighty and Eighty Pisas Only
5	I.S.I Marked 40mm dia X 2 mtr long UPVC RIBEED Strainer confirming to IS:12818-1983/1992	48 Nos.	Each	Rs.248.00	Rupees Two Hundred Forty Eight Only
6	I.S.I Marked 125 mm X 40 mm UPVC reducing socket (Heavy quality).	24 No.	Each	Rs.275.00	Rupees Two Hundred Seventy Five Only
7	Supplying all labour and material and fitting and fixing G.I. cap over the new sunked T/well	24 No.	Each	Rs.144.08	Rupees One Hundred Forty Four and Eight Pisas Only
8	Providing all material and labour and construction 1.85m dia circular PCC (1:2:4) UNICEF design platform with foot rest etc. all complete.	24 No.	Each	Rs.4,389.00	Rupees Four Thousand Three Hundred Eighty Nine Only
9	Providing all material and construction of P.C.C. (1:2:4) UNICEF design drain for disposal of water etc. all complete.	72 M	P/M	Rs.487.00	Rupees Four Hundred Eighty Seven Only
1	Boring by jet dhaki by suitable cutter or reduce as the case may be lowering 125 mm U.P.V.C. X 40mm dia UPVC pipe & strainer of standard quality iron shoe, plug & socket etc. all complete including providing all tools and plants required for the job as per specification and direction of the engineer in charge.				
	(i) 0 to 30.5m				
	(a) For 125 mm dia U.P.V.C. pipe	648.0 M	P/M	Rs.270.00	Rupees Two Hundred Seventy Only
	(b) For 40 mm dia UPVC Pipe	84.0 M	P/M	Rs.153.70	Rupees One Hundred Fifty Three and Seventy Pisas Only

Bambam Singh

Bambam Singh
Execution Engineer
P.H. Division Patna East, Patna

S. N.	Particulars	Qty.	Unit	Rate	Rate in Wo
	(ii) 30.5 m to 46.0 m	372.0 M	P/M	Rs. 176.80	Rupees One Hundred Seventy Six and Eighty Pisas Only
2	Providing all labour & tools and fitting & fixing India mark II hand pump over newel sunked T/Well etc. all Complete.	24 No.	Each	Rs. 129.70	Rupees One Hundred Twenty Nine and Seventy Pisas Only
3	Providing all labour & tools and lowering 32mm dia G.I. pipe as per specification etc. all Complete.	576 M	P/M	Rs 20.32	Rupees Twenty and Thirty Two Pisas Only
4	Providing all labour & tools and fitting & fixing Cylinder with requisite suspension pipe and connection rod of India mark III hand pump etc. all Complete.	24 No.	Each	Rs. 122.90	Rupees One Hundred Twenty Two and Ninety Pisas Only
5	Supplying labour and developing the T/Well to have sand free discharge all complete as per direction of E/I	24 No.	Each	Rs. 357.80	Rupees Three Hundred Fifty Seven and Eighty Pisas Only
6	Transportation of material & tools from Store to work site and back to	24 No.	Each	Rs. 290.00	Rupees Two Hundred Ninety Only
7	Supplying all materials, labour and writing on each hand pump, the name of work, name of contractor, Mobile No., Name of	24 Job	Each	Rs. 50.00	Rupees Fifty only
Maintenance of Hand Pumps for 5-Years					
	Supplying all labours, tools, plants & materials for maintenance of Hand Pumps up to 5-Years from the end of defects & liabilities period i.e. 6-Months from the date of final measurement of work.	24 Job	Each	Rs. 4,900.00	Rupees Four Thousand Nine Hundred Only

Construction of 48 Nos. 125mm x 40mm x 61M deep Tube Well with L.M.-II Hand Pump, Platform & drain including Operation & Maintenance for 5 years in Patna district.

S. N.	Particulars	Qty.	Unit	Rate	Amount
1	CONSTRUCTION OF 125MM X 40MM X 61M DEEP T/WELL				
Part 'A' Cost of Materials					
1	I.S.I Marked India mark II hand pump with 8 Nos. Connecting Rod and one cylinder confirming IS:15500(Part 1-8)/2008	48 No.	Each	Rs. 9,284.00	Rupees Nine Thousand Two Hundred Eighty Four Only
2	I.S.I Marked 125mm dia U.P.V.C. casing pipe confirming to IS:12818-1983/1992	1296 M	P/M	Rs. 432.00	Rupees Four Hundred Thirty Two Only
3	I.S.I Marked 32 mm dia G.I. pipe medium quality (3mtr each length) confirming IS:1239(Part 1-4)	1152 M	P/M	Rs. 234.00	Rupees Two Hundred Thirty Four Only
4	I.S.I Marked 40mm dia best quality UPVC pipe conforming to IS:12818-1983/1992	1440 M	P/M	Rs. 80.80	Rupees Eighty and Eighty Pisas Only
5	I.S.I Marked 40mm dia X 2 mtr long UPVC RIBBED Strainer confirming to IS:12818-1983/1992	96 Nos.	Each	Rs. 248.00	Rupees Two Hundred Forty Eight Only
6	I.S.I Marked 125 mm X 40 mm UPVC reducing socket (Heavy quality)	48 No.	Each	Rs. 275.00	Rupees Two Hundred Seventy Five Only
7	Supplying all labour and material and fitting and fixing G.I. cap over the new sunked T/well	48 No.	Each	Rs. 144.08	Rupees One Hundred Forty Four and Eight Pisas Only
8	Providing all material and labour and construction 1.85m dia circular PCC (1:2:4) UNICEF design platform with foot rest etc. all complete.	48 No.	Each	Rs. 4,389.00	Rupees Four Thousand Three Hundred Eighty Nine Only
9	Providing all material and construction of P.C.C. (1:2:4) UNICEF design drain for disposal of water etc. all complete.	144 M	P/M	Rs. 487.00	Rupees Four Hundred Eighty Seven Only
Part 'B' Labour Cost (Classification of soil item 'B')					

Bambamish

501
Executive Engineer
 P.M. Division Patna East, Patna

No.	Particulars	Qty.	Unit	Rate	Rate in Words
1	Boring by jet dheki by suitable cutter or reduce as the case may be lowering 125 mm U.P.V.C. X 40mm dia UPVC pipe & strainer of standard quality iron shoe, plug & socket etc. all complete including providing all tools and plants required for the job as per specification and direction of the engineer in charge				
	(i) 0 to 30.5m				
	(a) For 125 mm dia U.P.V.C. pipe	1296.0 M	P/M	Rs.270.00	Rupees Two Hundred Seventy Only
	(b) For 40 mm dia UPVC Pipe	168.0 M	P/M	Rs.153.70	Rupees One Hundred Fifty Three and Seventy Pisas Only
	(ii) 30.5 m to 61.0 m	1464.0 M	P/M	Rs.176.80	Rupees One Hundred Seventy Six and Eighty Pisas Only
2	Providing all labour & tools and fitting & fixing India mark II hand pump over newel sunked T/Well etc. all Complete.	48 No	Each	Rs.129.70	Rupees One Hundred Twenty Nine and Seventy Pisas Only
3	Providing all labour & tools and lowering 32mm dia G.I. pipe as per specification etc. all Complete.	1152 M	P/M	Rs.20.32	Rupees Twenty and Thirty Two Pisas Only
4	Providing all labour & tools and fitting & fixing Cylinder with requisite suspension pipe and connection rod of India mark III hand pump etc. all Complete.	48 No.	Each	Rs.122.90	Rupees One Hundred Twenty Two and Ninety Pisas Only
5	Supplying labour and developing the T/Well to have sand free discharge all complete as per direction of E/I	48 No.	Each	Rs.357.80	Rupees Three Hundred Fifty Seven and Eighty Pisas Only
6	Transportation of material & tools from Store to work site and back to.	48 No.	Each	Rs.290.00	Rupees Two Hundred Ninety Only
7	Supplying all materials, labour and writing on each hand pump, the name of work, name of contractor, Mobile No., Name of the department etc. to facilitate, ease of maintenance including the photographs in soft and hard copy for fixing of tubewell and completed hand pump with platform and drain in water discharging position etc alongwith computerised booklet in soft and hard copy of completed scheme all complete as per direction of E/I.	48 Job	Each	Rs.50.00	Rupees Fifty only
2	Maintenance of Hand Pumps for 5-Years				
	Supplying all labours, tools, plants & materials for maintenance of Hand Pumps up to 5-Years from the end of defects & liabilities period i.e. 6-Months from the date of final measurement of work.	48 Job	Each	Rs.4,900.00	Rupees Four Thousand Nine Hundred Only


Executive Engineer
P.H. Division, Patna East, Patna

Rate approved 3.91% (Three point Nine One Percent) below the estimated rate by The Suprintending Engineer, P.H.E. Circle Patna Circle, Patna vide letter no.-407 dt. 22.05.14


Supt. Engineer
P.H. Division, Patna East, Patna

Bambamish